

Picnic Table Platform:

A picnic table has existed in the Bigelow Springs Park for a few years. It moves around, and is never on level ground. This proposal is to make a level platform for it to rest on.

- An 8' x 10' site would be dug down and leveled, such that the eventual platform would be at least 1" above the surrounding grass along any edge.
- The platform would be framed by pressure treated 2" x 6"s, moored to the ground every 2.5 linear feet with 1-foot-long, 1/2" rebar.
- Weed cloth would be secured beneath the future gravel
- 1.5 cubic yards of decomposed, compacted granite gravel (or concrete, if preferred) would be placed.

The location would be arranged with OPARD, but two likely spots are shown at right:

Material Cost **About \$270**

Purpose	Material	Amount	Cost
Frame	PT 2" x 6"	40 LF	\$46.00
Rebar	1/2" x 1'	12	\$8.00
Weed Cloth	Weed Cloth	100 sf	\$12.00
Gravel	decomposed granite	1.5 yds	\$200.00
		Total	\$266.00



Labor Cost: **About \$400**

Job Done	Hours	Cost (\$26.72/hr)
Excavate site	8	\$213.76
Build and stake frame	3	\$80.16
Weed cloth, install gravel, pack	4	\$106.88
	Total	\$400.80

Total Cost = \$670